

SURVEY LEGEND

- STORM WATER LINE
- SS — SANITARY SEWER LINE
- OHW — OVERHEAD WIRES
- IPF = IRON PIPE FOUND
- R/W = RIGHT OF WAY
- N/F = NOW OR FORMERLY
- RCP = CONC. STORM PIPE
- DIP = DUCTILE IRON PIPE
- Typ. = TYPICAL
- T/C = TOP OF CURB
- TVC = TOP OF VALLEY CURB
- INV = INVERT ELEVATION
- ⊕ TEMP. BENCH MARK
- ⊕ WATER METER
- ⊕ FIRE HYDRANT
- ⊕ WATER VALVE
- ⊕ SANITARY MANHOLE
- ⊕ SANITARY CLEANOUT
- ⊕ CAST IRON CATCH BASIN
- ⊕ TELEPHONE PEDESTAL
- ⊕ ELEC. CABINET
- ⊕ SIGN

SURVEY NOTES:

THIS SURVEYOR DID NOT PERFORM A BOUNDARY SURVEY IN CONJUNCTION WITH THE PRESENT MAPPING. ALL BOUNDARY INFORMATION IS SHOWN PER PB 2005 PG 150, ORIENTED TO PROPERTY MONUMENTATION RECOVERED, AS SHOWN HEREON.

THERE MAY BE EASEMENTS, RIGHTS-OF-WAY, OR OTHER MATTERS AFFECTING THIS PROPERTY WHICH ARE NOT SHOWN HEREON.



SITE BENCHMARKS WERE ESTABLISHED BY DIFFERENTIAL STATIC GPS METHODS USING THREE PROMARK II GPS RECEIVERS HOLDING NCG MONUMENT "GUNTER" (ELEV = 418.86 FEET) AS A FIXED VERTICAL REFERENCE. THE VERTICAL DATUM IS NAVD 88 WITH A PRECISION OF 0.006" AT THE 95% CONFIDENCE LEVEL.

ALL DISTANCES ARE HORIZONTAL GROUND MEASUREMENTS UNLESS NOTED OTHERWISE.

ACCORDING TO FEMA FLOOD INSURANCE RATE MAP COMMUNITY PANEL #3710975100-J, EFFECTIVE 02 FEBRUARY, 2007, THIS SITE DOES NOT LIE WITHIN THE 100-YEAR OR OTHER SPECIAL HAZARD FLOOD ZONE.

ANY UNDERGROUND IMPROVEMENTS ARE SHOWN BASED ON SURFACE EVIDENCE ONLY. THIS SURVEYOR CANNOT CERTIFY TO NOR ACCEPT LIABILITY FOR THE PRESENCE AND/OR LOCATION OF BURIED OR OTHERWISE NON-VISIBLE IMPROVEMENTS.

THIS LOT MAY BE SUBJECT TO CONDITIONS, COVENANTS, AND RESTRICTIONS PER DB 1174 PG 181 AND PER PB 2005 PG 105.



SITE DATA:

TOTAL ACREAGE:	0.828± ACRES
PIN#:	9751-26-9608
TAX PARCEL:	82340
ZONING:	C-2
P.B./PG:	2005-105
D.B./PG:	1174-181

PARKING DATA:

PARKING REQUIREMENTS:	1/200 S.F.
4486 S.F./200 = 22 SPACES REQ'D.	
TOTAL SPACES REQUIRED:	22 SPACES
TOTAL SPACES PROVIDED:	22 SPACES

GENERAL NOTES:

- CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES PRIOR TO BEGINNING ANY EXCAVATION.
- BOUNDARY AND TOPOGRAPHIC INFORMATION TAKEN FROM A MAP PREPARED BY SACKS SURVEYING & MAPPING, PC, 3308-B EDGEFIELD ROAD, GREENSBORO, NC, 27409 (336) 931-0566. CONTRACTOR SHALL VERIFY EXISTING CONDITIONS PRIOR TO STARTING WORK.
- THIS SITE IS LOCATED IN THE JORDAN LAKE WATERSHED. STORMWATER FROM THE DEVELOPED PROPERTY SHALL DISCHARGE TO THE EXISTING DETENTION POND LOCATED AT THE SOUTHWEST CORNER OF THE BUSINESS PARK. THIS PROPERTY HAS VESTED RIGHTS TO UTILIZE THE EXISTING DETENTION POND FOR WATER QUALITY. MAINTENANCE OF THE EXISTING POND IS THE RESPONSIBILITY OF THE DEVELOPER AND/OR OWNER'S ASSOCIATION.
- THIS PROPERTY IS NOT LOCATED IN A SPECIAL FLOOD HAZARD ZONE AS DETERMINED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP No. 3710975100J DATED FEBRUARY 2, 2007. SOIL TYPES PER CHATHAM COUNTY GIS: Cb & Gb2. AVERAGE SITE SLOPE: 1-3 PERCENT.
- CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL DURING WORK IN PUBLIC STREETS IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) AND THE REQUIREMENTS OF THE TOWN OF PITTSBORO.
- DIMENSIONS ARE TO PROPERTY LINE, FACE OF CURB, EDGE OF PAVEMENT, CENTERLINE OF STRIPE, OR FACE OF BUILDING/STRUCTURE UNLESS OTHERWISE NOTED.
- SEE ARCHITECTURAL PLANS FOR BUILDING INFORMATION.
- ALL VEHICULAR SIGNAGE SHALL CONFORM TO THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). SIGNS SHALL BE MOUNTED IN ACCORDANCE WITH NCDOT STANDARD DETAIL 904.50.

UTILITY NOTES:

- MATERIALS AND CONSTRUCTION OF SANITARY SEWER AND WATER SHALL CONFORM TO THE TOWN OF PITTSBORO AND NORTH CAROLINA DIVISION OF WATER QUALITY STANDARDS, LOCAL AND STATE PLUMBING CODES.
- ALL ON-SITE PRIVATE WATER AND SANITARY SEWER LINES SHALL BE MAINTAINED BY THE PROPERTY OWNER.
- WATER METER AND BACKFLOW PREVENTER SHALL CONFORM TO TOWN OF PITTSBORO STANDARDS.
- ALL STANDARD MGDENR AND TOWN OF PITTSBORO REQUIRED UTILITY SEPARATIONS SHALL BE PROVIDED.
- COORDINATE WITH PLUMBING DRAWINGS FOR SIZE, DEPTH AND LOCATION OF WATER AND SANITARY SEWER UTILITIES INTO BUILDING.
- THIS FACILITY WILL NOT BE SPRINKLERED.
- ANY DAMAGE TO EXISTING UTILITIES TO REMAIN CAUSED BY CONSTRUCTION ACTIVITIES SHALL BE REPAIRED BY THE CONTRACTOR.

OWNER:
PITTSBORO FEED
1103 EAST STREET
PITTSBORO, NC. 27312
(919) 542-2454

CONTRACTOR:
BAR CONSTRUCTION CO. INC.
611-A INDUSTRIAL AVE.
GREENSBORO, NC. 27406
(336) 274-2477

Revision	Description	By	Date



FINAL DRAWINGS RELEASED FOR CONSTRUCTION	<input type="checkbox"/>
DATE: 6/16/14	<input type="checkbox"/>
FINAL DRAWINGS RELEASED FOR CONSTRUCTION	<input type="checkbox"/>
DATE: 6/16/14	<input type="checkbox"/>
PRELIMINARY DRAWINGS FOR CONSTRUCTION	<input type="checkbox"/>
DATE: 6/16/14	<input type="checkbox"/>

CivilDesigns, P.A.
Consulting Civil and Environmental Engineering
3817-C Lawndale Drive, Greensboro, North Carolina 27455
Phone: (336) 282-5542 Fax: (336) 282-5592
N.C. License No. C-1043

SITE/UTILITY PLAN	
A PROPOSED BUILDING FOR PITTSBORO FEED	
COMMERCE CT	
DESIGNED BY: K. BRODERICK	DATE: 6/16/14
DRAWN BY: D. RUSSELL	PROJECT # 14230

